

BARANAGAR MUNICIPALITY

TENDER NOTICE NO: 038/PW/15-16

No. PW/038/1-15-16 Date 21/8/15

M/s.....

SEALED Tender is invited and will be received by the Chairman up to 3 P.M of 31.08.2015 for the following work as per terms and condition given below.

The Tender should be addressed to the Chairman, superscripted for "CONSTRUCTION OF SEPTIC TANK AT HOSPITAL BUILDING OF THIS MUNICIPALITY."

LAST DATE OF DROPPING- ^{31.} 29.08.2015

SL. NO	WORK DESCRIPTION	TENDER AMOUNT Rs.	STIPULATED PERIOD
01.	CONSTRUCTION OF SEPTIC TANK AT HOSPITAL BUILDING OF THIS MUNICIPALITY."	97,828.00	As per Office Direction. 15 DAYS.

m.m.s. 21/8/15
E.O./F.O.

TERMS & CONDITION

21/8/15
CHAIRMAN.

- 1) Tenders to be submitted in the prescribed tender Form which will have to be obtained from the Municipality at a prescribed cost or Demand draft of Rs.200/- attached with the form downloaded from our website www.baranagarmunicipality.org.
- 2) Tenderer must be registered under " West Bengal Building and other Contribution Welfare Cess ,E.P.F & E.S.I Act. otherwise it will not be treated as valid.
- 3) Earnest Money of 2 % of the estimated cost should be deposited along with the tender.
- 4) The stipulated date for commence / completion of work as per work order issued will have to strictly followed.
- 5) Successful Tenderer (work above Rs.5000/-) shall have to execute a formal Agreement with the Municipality within a week from the date of intimation of the acceptance of his Tender at his own cost & risk.
- 6) The Chairman also reserves the right of accepting of canceling any Tender without assigning any reason thereof.
- 6) If the successful tenderer fails to complete the job within the specified time, a fine of at a stipulated rate(Rs.25/- per day)as fixed by the Municipal Authority will be levied.
- 7) All Tenders are to be drop in the "Tender dropping Box" kept in the Chairman's room otherwise it will not be treated as valid.

Estimate No - 002/BMPW/Tank/15-16

BARANAGAR MUNICIPALITY					
Estimate for construction of Septic Tank at Hospital Bldg.					
Sl no	Description of item	Qty	Unit	Rate	Amount
1	Construction of septic tank of different capacities as per approved drawing with 1st class brick work in cement mortar (1:4) including two 560 mm dia. R.C.C. manhole cover (heavy type) of approved make supplied, fitted and fixed in the 100mm thick R.C.C (1:1.5:3) top slab with necessary fittings, 20mm thick cement plaster (4 : 1) with neat cement finish to the internal surfaces and 15 mm thick cement plaster (4 : 1) to outside wall upto 200 mm below G.L floor finished with 25 mm thick grey artificial stone over 100 mm thick R.C.C (1:1.5:3) bottom slab including supplying, fitting and fixing all necessary specials, fittings, S.W. tees, C.I. foot rest etc. including excavation earth in all sorts of soil, shoring, bailing out and pumping out water as necessary, ramming, dressing the bed and fefilling the sides of the tanks with earth, removing spoils, filling up the chamber with clear water, removing foreign materials from the chamber and including constructing attached inspection pit as per approved drawing and connecting all necessary pipes, joints etc. with internal plaster work and artificial stone flooring is to be done with admixture of water proofing compound @ 0.5% by weight of cement with all costs of labour and materials				
	(iii) For 30 user				
	A) With Pakur variety.	1	Each	68982	68982.00

2	Supplying, fitting and fixing PVC pipes of approved makeof (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials Payment for painting will be made seperately)				
	100 mm	1.5 mt	1200	1800.00	
3	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes.				
	(i) Pakur Variety	1.2 Cum	5389	6466.80	
4	Brick work with 1st class bricks in cement mortar (1:6)				
	(a) In foundation and plinth	1.5 Cum	5719	8578.50	
	(b) In superstructure, ground floor	1.7 Cum	5943	10103.10	
5	Dismantling all types of plain cement concrete works, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m In ground floor including roof.				
	a) upto 150 mm. thick	2.0 Cum	949	1898.00	
				97828.40	
			Add Cess 1%	978.28	
			Add Contingency 3%	2934.85	
				101741.53	
				101742.00	



