

## BARANAGAR MUNICIPALITY

TENDER NOTICE NO: 105/PN/16-17

No. PN/105/1-16-17 Date: 8/11/16

M/s.....

**SEALED** Tender invited and will be received by the Chairman up to 3 P.M of 23.11.2016 for the following work as per terms and condition given below.

The Tender should be addressed to the Chairman, superscripted for " **CONSTRUCTION OF DRAIN & ROAD AT WARD NO -11 UNDER THIS MUNICIPALITY. "**

**LAST DATE OF DROPPING-23.11.2016**

SL .NO	WORK DESCRIPTION	PUT TO TENDER AMOUNT	STIPULATED PERIOD
1.	Repairing of Drain near 16/1,21/3/A,14/14, Barrister P Mitra Road , 31/2, Neogi Para Road , Rep. of Road from 20, B.P. Mitra Road to crossing of Neogi Para Road and Lotus Club to Taltala Math. Ward No: 11.	Rs. 4,26,016.00	30 Days
2.	Improvement of Municipal Road near Lotus Club, 22/A/2, Barrister P Mitra Road, 34, Bonowari Lal Dhole Lane & Drain 119/3/1, 8/1/A, Neogi Para Road & 18-36, Bonowari Lal Dhole Lane. Ward-11.	Rs. 4,53,202.00	30 Days.
3.	Imp. of Municipal Road near 8/1/A, Neogi Para Road & 18-36 , Bonowari Lal Dhole lane. Ward 11	Rs. 4,62,074.00	30 Days .

*M.M. 8/11/16*  
E.O./F.O.

*Chairman 8/11/16*  
CHAIRMAN.

### TERMS & CONDITION

- 1) Tenders to be submitted in the prescribed tender Form which will have to be obtained from the Municipality at a prescribed cost or Demand draft of Rs.200/- attached with the form downloaded from our website [www.baranagarmunicipality.org](http://www.baranagarmunicipality.org).
- 2) **Tenderer must be registered under " West Bengal Building and other Contribution Welfare Cess ,E.P.F & E.S.I Act. otherwise it will not be treated as valid.**
- 3) **Earnest Money of 2 % of the estimated cost should be deposited along with the tender.**
- 4) The stipulated date for commence / completion of work as per work order issued will have to strictly followed.
- 5) Successful Tenderer (work above Rs.5000/-) shall have to execute a formal Agreement with the Municipality within a week from the date of intimation of the acceptance of his Tender at his own cost & risk.
- 6) The Chairman also reserves the right of accepting of cancelling any Tender without assigning any reason thereof.
- 6) If the successful tenderer fails to complete the job within the specified time, a fine of at a stipulated rate( Rs.25/- per day )as fixed by the Municipal Authority will be levied.
- 7) **All Tenders are to be drop in the "Tender dropping Box" kept in the Chairman's room otherwise it will not be treated as valid.**

# BARANAGAR MUNICIPALITY Page - 1

Repairing of Drain Near 16/1, 21/3/A,,14/14 Barister P. Mitra Road, 31/2, Neogi para Road, Rep. of Road from 20, B.p. maitra Road to crosiing of Neogi Para Road and Lotus Club to taltala Math,

## Ward -11

DESCRIPTION	No.	Measurement			Quantity	Unit	Rate	Amount	
		L	B	H					
1) Dismantling Brick Work	1	18	0.25	0.6	2.7	m3	451	1217.7	
16/1, Barister P. Mitra Road									
2) Single brick flat soling of									
picked jama bricks including									
ramming and dressing bed to									
proper level and filling joints									
with local sand. (P - 11/1 - 1 &	1	18	0.6	0	10.8				
P - 188/1 - 2/a)	42	3.45	1	0	144.9				
	18	2.2	1.75	0	69.3				
	1	4	0.68	0	2.72				
	1	3.5	3.6	0	12.6				
14/14, Barister P. Mitra	1	19	0.55	0	10.45				
Road	1	74	0.55	0	40.7				
31/2, Neogi Para Road.					291.5	m2	377	109884.19	
3) Cement concrete (1:2:4)	1	18	0.6	0.075	0.81				
	1	4	0.68	0.075	0.204				
	1	19	0.55	0.075	0.784				
	1	74	0.55	0.075	3.053				
					4.85	m3	6124	29702.931	
4) Brick work (1:6)	1	18	0.25	0.6	2.7				
	1	4	0.25	0.4	0.4				
	1	19	0.25	0.3	1.425				
	1	74	0.25	0.5	9.25				
					13.78	m3	5719	78779.225	
5) Hire & Labour Charges	13	0.7	0.39	0	3.549	m2	360	1277.64	
6) Rerinforcement for									
R.C.C.	52	0.7	0.39	0	14.2	Kg	61.93	879.15828	

221740.8443

221740.8443									
Cement concrete 1:1.5:3) STRUT	13	0.7	0.13	0	1.183				
to Neogi Para Road Crossing	23	3.45	1	0.075	5.95				
	19	3.45	1	0.1	6.555				
From Lotus Club - Taltala Math	18	2.2	1.75	0.1	6.93				
Depression	1	3.5	3.6	0.1	1.26				
					21.88	m3	6863	150148.714	
8) 10mm thick plaster (1:4) & neat cement punning	1	18	1.2	0	21.6				
	1	4	1.48	0	5.92				
	1	19	0.85	0	16.15				
	1	74	1.05	0	77.7				
					121.4	m2	178	21603.86	
9) Earth Work in excavation	42	3.45	1	0.15	21.74				
	18	2.2	1.75	0.18	12.47				
21/3/A, B.P. Maitra Road	1	4	0.68	0.55	1.496				
Depression	1	3.5	3.6	0.6	7.56				
14/14, B.P. Maitra Road	1	19	0.55	0.45	4.703				
31/2, Neogi Para Road	1	74	0.55	0.65	26.46				
					74.42	m3	120.47	8965.678575	
10) Removal of Rubish	42	3.45	1	0.15	21.74				
	18	2.2	1.75	0.18	12.47				
	1	4	0.68	0.55	1.496				
	1	3.5	3.6	0.6	7.56				
	1	19	0.55	0.45	4.703				
	1	74	0.55	0.65	26.46				
					74.42	m3	168	12502.98	
11) 125 mmth. Brick work (1:4)	1	4	0.4	0	1.6				
	1	19	0.3	0	5.7				
					7.3	m2	783	5715.9	
12) Silver sand filling	1	3.5	3.6	0.43	5.418	m3	985.24	5338.03032	
								426016.0072	

Assistant Engineer  
P.W. Department  
Baranagar Municipality

Chairman  
Baranagar Municipality


# BARANAGAR MUNICIPALITY

for Imp. of Municipal rd near Lotus club, 22/A/2, Barister P.M. rd 34, Bonowari L.D. Lane & Drain  
1, 8/1/A, neogi para rd & 18;36, Bonowari L.D. Lane. ward-11

DESCRIPTION	No.	Measurement			Quantity	Unit	Rate	Amount
		L	B	H				
Cement concrete (1:1.5:3) lotus club,	1	56	1.1	0.075	4.62			
40 neogi para rd	1	17	1.85	0.075	2.35875			
22/A/2 Barister P.M. road	1	40	1.55	0.075	4.65			
	1	1.4	0.8	0.1	0.112			
	1	3.4	1.2	0.15	0.612			
	1	3	1.2	0.075	0.27			
	2	66	0.3	0.15	5.94			
	1	10	1.2	0.075	0.9			
34, Bonowari L.D. Lane	1	66	3	0.075	14.85			
					34.31	m3	6863	235488.40
2) Picking up. Bonowari L.D. Lane	34, 1	66	3	0	198			
3) Single Brick Flat Soling	1	1.4	0.8	0	1.12			
	1	26	0.28	0	7.28			
	1	3.4	1.2	0	4.08			
					12.48	m2	377	4704.96
4) Removal of rubbish	1	1.4	0.8	0.75	0.84			
	1	26	0.28	0.3	2.184			
	1	3.4	1.2	0.65	2.652			
	1	66	3	0.15	29.7			
					35.376	m3	168	5943.17
5) Brick Work (1:6)	1	12	0.25	0.1	0.3			
	32	0.35	0.25	0.75	2.1			
	1	90	0.375	0.1	3.375			
	2	1.4	0.25	0.6	0.42			
119/3/1, neogi Para Rd	1	13	0.375	0.1	0.4875			
	2	3.4	0.375	0.5	1.275			
	1	86	0.375	0.2	6.45			
	2	17	0.25	0.25	2.125			
	2	66	0.25	0.1	3.3			
					19.83	m3	5719	113422.07
6) 125 mm th. Brick Work(1:4)	1	73	0.1	0	7.3			
	1	26	0.15	0	3.9			
	2	66	0.1	0	13.2			
					24.4	m2	783	19105.2
							<b>TOTAL -</b>	<b>378663.80</b>

P.T.O.

DESCRIPTION	No.	Measurement			Quantity	Unit	Rate	Amount
		L	B	H				
am th Plaster (1:4) & New Cement	1	73	0.23	0	16.79		B/F	378663.80
	1	12	0.35	0	4.2			
	32	0.35	1	0	11.2			
	1	90	0.48	0	43.2			
	1	1.4	1.5	0	2.1			
	1	13	0.9	0	11.7			
	1	26	0.43	0	11.18			
	1	13	0.48	0	6.24			
	1	3.4	1.45	0	4.93			
	1	86	0.6	0	51.6			
	1	17	0.5	0	8.5			
	2	66	0.58	0	76.56			
					248.2	m2	178	44179.6
8) Earth Wark								
	1	1.4	0.8	0.75	0.84			
119/3/5, Neogi Para Rd	1	26	0.28	0.3	2.184			
18-36 Bonowari Dhole Ln	1	3.4	1.2	0.65	2.652			
					5.676	m3	120.47	683.79
9) Cement Concrete (1:2:4)								
	1	1.4	0.8	0.075	0.084			
	1	26	0.28	0.075	0.546			
	1	3.4	1.2	0.075	0.306			
					0.936	m3	6124	5732.06
10) Hire & Labour								
	1	1.4	0.3	0	0.42			
	2	2.2	0.1	0	0.44			
	1	3.4	0.45	0	1.53			
	2	4.6	0.15	0	1.38			
					3.77	m2	360	1357.2
11) Reinforcement								
	10	0.8	0.39	0	3.12			
	6	1.4	0.39	0	3.276			
	23	2	0.89	0	40.94			
	12	3.4	0.39	0	15.912			
	21	1.2	0.39	0	9.828			
	8	3	0.39	0	9.36			
	67	1.2	0.39	0	31.356			
	8	10	0.39	0	31.2			
					144.992	Kg	61.93	8979.35
12) Disanting R.C.C.								
	1	3.4	1.2	0.15	0.612	m3	1975	1208.7
13) Brick on End Edging								
	2	66	0	0	132	m	93.92	12397.44
TOTAL -								453201.95


  
 Asst. Engineer  
 P.W.D  
 Assistant Engineer  
 P.W. Department  
 Baranagar Municipality


  
 Chairman  
 Baranagar Municipality  
 Chairman

# BARANAGAR MUNICIPALITY

Rate for Imp. of Municipal rd near 8/1/A, neogi para rd & 18-36, Bonowari L.D. Lane. ward-11

DESCRIPTION	No.	Measurement			Quantity	Unit	Rate	Amount
		L	B	H				
1) Picking up. 8/1/A, neogi para rd	1	90	3.25		292.5			
18 & 36, Bonowari L.D. Lane	1	86	3.6		309.6			
					602.1	m2	12.9	7767.09
2) Single Brick Flat Soling	1	4	3.3		13.2	m2	377	4976.4
3) Removal of rubbish	1	90	3.25	0.15	43.875			
	1	86	3.6	0.15	46.44			
					90.315	m3	168	15172.92
4) Ready Mixed Concrete (1:1.5:3) With Pump								
8/1/A, Neogi Para rd	1	90	3.25	0.075	21.94			
8/1/A, Neogi Para rd	1	12	1.1	0.075	0.99			
18-36 Bonowari L.D. Ln	1	86	3.6	0.1	30.96			
					53.89	m3	7944	428082.3
5) Jhama Matal Consolidation	1	90	0.33	0.075	2.23	m3	2727.4	6075.28
TOTAL -								462073.99

  
 Asst. Engineer  
 P.W.D  
 Assistant Engineer  
 P.W. Department  
 Baranagar Municipality

  
 Chairman  
 Baranagar Municipality  
 Chairman  
 Baranagar Municipality