



BARANAGAR MUNICIPALITY
87 DESHBANDHU ROAD KOLKATA 35


SPECIFIC PRICE SHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF
IMP OF PASSAGE OF 80-90 S P BANERJEE ROAD

ESTIMATE NO 041/PW/Dept./05

WARD NO - 5

SL NO - 6

SI No	Description of Items	Qty	Unit	Rate	Amount
1	Labour for taking out old solling edging including removing debris a) Single brick flat solling page no.397 item no. 6(a)	396.00	m2	6.07	2403.72
2	Labour for laying solling with departmental bricks including including carriage of departmental bricks within a lead of 150 m preparation of bed as necessary with bricks joint properly field inand packed with bricks joints properly field in and packed with local sand or powder earth and including necessary quassion of similar material below the solling (and in between layers when more than one layer in use) the item included the cost of optaining local sand of powder earth a) single brick flat solling (thickness 75 mm)	237.60	m2	25.18	5982.77
3	125 mm thick brikwork with 1st class bricks in cement mortar 1:4 page no. 73 Item no, 29 PWD Bldg	55.00	m2	677.00	37235.00
4	10 Mm thick cement pluster with sand & cement morther (4:1)with 1.5 Mm thick neat cement punningr page no. 319 Item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg	198.00	m2	124.29	24609.42
5	Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used) complets asper direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG	158.40	m2	340.00	53856.00
6	Filling in foundation or plinth by silver sand in layers not exceeding 150 MM as directed and consolidating the same by through saturation with water ramming complate including the cost of supply of sand.(Payment to be made on measuremnet of finished quantity. Page no. 5 Item no. 4 A PWD BLDG	29.70	m3	583.00	17315.10



7	Brick work with 1st class in cement mortar (1:6) in foundation and plinth page no. 69 Item no, 21(a) PWD Bldg	13.75	CUM	4999.00	68736.25
8	Ordinary cement concrete (Mix 1:1.5:3) with graded stone chips (20mm nominal size) excluding shuttering and reinforcement if any in ground floor as per relevant IS code i) pakur variety p no 39 item no 7 (i) PWD BLDG	29.70	CUM	5675.32	168557.00

SAY

378695.26
378695.00

[Signature]
Assistant Engineer
P.W. Department
Baranagar Municipality

[Signature] 19/9/12.
Chairman
Baranagar Municipality