



BARANAGAR MUNICIPALITY
87 DESHBANDHU ROAD KOLKATA 35

SPECIFIC PRICE SHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF
CONSTRUCTION OF DRAIN AT 111 D B ROAD (W)

ESTIMATE NO B43/PW/Dept/07 WARD NO-7 SL NO-8

SI No	Description of Items	Qty	Unit	Rate	Amount
1	125 mm thick brikwork with 1st class bricks in cement mortar 1:4 page no. 73 Item no, 29 PWD Bldg	10.50	m2	677.00	7108.50
2	10 Mm thick cement pluster with sand & cement morthor (4:1)with 1.5 Mm thick neat cement punningr page no. 319 Item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg	118.90	m2	124.29	14778.08
3	Cement concrete with graded jhamakua(30MM size) excluding shuttering a)1:3:6 proporton page no 33 item no. 4 A	1.41	m3	4766	6720.06
4	Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used) complets asper direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG	43.90	m2	340.00	14926.00
5	Brick work with ist class in cement mortar (1:6) in foundation and plinth page no. 69 Item no, 21(a) PWD Bldg	17.62	CUM	4999.00	88082.38




6	Earth work in in excavation of foundation trenches or drains in all sorts of soil (including mixed soil but excluding laterite or sanstone) including removing spreading or stacking the spoils within a lead of 75 meters directed. The items includes necessary trimmiing the sides of trenches , labelling, dressing and ramming the bottom, the bailing out the water as required complete. a) depth of excavation not exceeding not 1500MM. page no. 1 item no. 2A.	5.67	m3	73.77	418.28
---	--	------	----	-------	--------

132033.30

SAY

132033


Assistant Engineer
P.W. Department
Baranagar Municipality


Chairman
Baranagar Municipality