



BARANAGAR MUNICIPALITY  
87 DESHBANDHU ROAD KOLKATA 35

SPECIFIC PRICE SHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF  
IMPROVEMENT OF PASSAGE OF 120 D B RD. (W)

ESTIMATE NO 044/PW/Dept/07


WARD NO-7


SL NO-9

SI No	Description of Items	Qty	Unit	Rate	Amount
1	125 mm thick brikwork with 1st class bricks in cement mortar 1:4 page no. 73 Item no, 29 PWD Bldg	7.20	m2	677.00	4874.40
2	10 Mm thick cement pluster with sand & cement morther (4:1)with 1.5 Mm thick neat cement punningr page no. 319 Item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg	30.00	m2	124.29	3728.70
3	Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containg designingned quantity of cement par CU.m of weight concrete produced in computerised batching under controlled condition using approved super plastisized designing concrete mix followibg IS 10262 & IS 456 transporting the mix with egutation in trabsit mixture to work site depositing the mix on aplatform erected for the purpose at requred lebe;s of concreteing and the placing the mix in its final locatio0n of form work compacting & curibg the same complete as per specification & direction of the Engineer --in -Charge including computerised batching plnat transit mixture witi all assesories vibratorsr etc inclusive of all other incidental charges in this connection complte but excluding cost of higher charge of platform and its supporting staging which would be paid through seperate item ( cement to be suplied by the manufactures or supplier .) i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLD	6.00	m3	6207.16	37242.96
4	Brick work with ist class in cement mortar (1:6) in foundation and plinth page no. 69 Item no. 21(a) PWD Bldg	1.8	CUM	4999.00	8998.20 54844.26

SAY

54844

  
Assistant Engineer  
P.W. Department  
Baranagar Municipality

  
Chairman  
Baranagar Municipality