



**BARANAGAR MUNICIPALITY**  
87 DESHBANDHU ROAD KOLKATA 35


SPECIFIC PRICE SHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF  
IMPROVEMENT OF PASSAGE OF OLAI CHANDI MANDIR AT R.K.M. RD.

ESTIMATE NO 045/PW/Dept/07

WARD NO-7

SL NO-10

SI No	Description of Items	Qty	Unit	Rate	Amount
1	Box cutting or filling in road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on burm to approx. gate and camber and rolling the sub grade with power roller to proper camber and grade as per direction and satisfaction of and grade as per direction and satisfaction of engineer in charge including uprooting and removings plants and jungles when and where necessary (a) upto 150 mm	27.75	SQM	9.60	266.40
2	125 mm thick brikwork with 1st class bricks in cement mortar 1:4 page no. 73 Item no, 29 PWD Bldg	15.00	m2	677.00	10155.00
3	10 Mm thick cement pluster with sand & cement morther (4:1)with 1.5 Mm thick neat cement punningr page no. 319 Item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg	49.20	m2	124.29	6115.07
4	Earth work in in excavation of foundation trenchesor drains in all sorts of soil ( including mixed soil but excluding laterrite or sanstone ) including removing spreading or stacking the spoils within a lead of 75 meteras directed. The items includes necessary trimmiing the sides of trenches , labelling, dressing and ramming the bottom, the bailing out the water as required complete. a) depth of excavation not exceeding not 1500MM. page no. 1 item no. 2A.	7.2	m3	73.77	531.14
5	Cement concrete with graded jhamakua(30MM size) excluding shuttering a)1:3:6 proporton page no 33 item no. 4 A	1.35	m3	4766	6434.10



6	<p>Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used ) complts asper direction</p> <p>a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG</p>	45.75	m2	340.00	15555.00
7	<p>Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containg designingned quantity of cement par CU.m of weight concrete produced in computerised batching under controlled condition using approved super plastisized designing concrete mix followibg IS 10262 &amp; IS 456 transporting the mix with egutation in trabsit mixture to work site depositing the mix on aplatform erected for the purpose at required lebe;s of concreteing and the placing the mix in its final locatio0n of form work compacting &amp; curibg the same complete as per specification &amp; direction of the Engineer --in -Charge including computerised batching plnat transit mixture witi all assesories vibratorsr etc inclusive of all other incidental charges in this connection complate but excluding cost of higher charge of platform and its supporting staging which would be paid through seperate item ( cement to be suplied by the manufactures or supplier .)</p> <p>i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLDG</p>	8.83	m3	6207.16	54809.22
8	<p>Brick work with ist class in cement mortar (1:6) in foundation and plinth page no. 69 Item no. 21(a) PWD Bldg</p>	0.9	CUM	4999.00	4499.10

98365.03

SAY

98365

*[Signature]*  
 Assistant Engineer  
 P.W. Department  
 Baranagar Municipality

*[Signature]* 19/9/12  
 Chairman  
 Baranagar Municipality