



BARANAGAR MUNICIPALITY
87 DESHBANDHU ROAD KOLKATA 35


SPECIFIC PRICE SHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF
IMPROVEMENT OF PASSAGE AT 35 D.N. CHATTERJEE. ROAD.

ESTIMATE NO 047/PW/Dept/08

WARD NO-8

SL NO-12

SI No	Description of Items	Qty	Unit	Rate	Amount
1	Box cutting or filling in road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on burm to approx. gate and camber and rolling the sub grade with power roller to proper camber and grade as per direction and satisfaction of and grade as per direction and satisfaction of engineer in charge including uprooting and removings plants and jungles when and where necessary (a) upto 150 mm	120	SQM	9.60	1152.00
2	125 mm thick brikwork with 1st class bricks in cement mortar 1:4 page no. 73 Item no, 29 PWD Bldg	24.00	m2	677.00	16248.00
3	10 Mm thick cement pluster with sand & cement morthor (4:1)with 1.5 Mm thick neat cement punningr page no. 319 Item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg	30.00	m2	124.29	3728.70
4	Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used) complets asper direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG	120.00	m2	340.00	40800.00



5	<p>Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containing designed quantity of cement per CU.m of weight concrete produced in computerised batching under controlled condition using approved super plastisized designed concrete mix following IS 10262 & IS 456 transporting the mix with egutation in trabsit mixture to work site depositing the mix on aplatform erected for the purpose at required lebe;s of concreteing and the placing the mix in its final locatio0n of form work compacting & curibg the same complete as per specification & direction of the Engineer --in -Charge including computerised batching plnat transit mixture with all assesories vibratorsr etc inclusive of all other incidental charges in this connection complte but excluding cost of higher charge of platform and its supporting staging which would be paid through seperate item (cement to be supplied by the manufactures or supplier .)</p> <p>i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLD</p>	9.00	m3	6207.16	55864.44
6	<p>Filling in foundation or plinth by silver sand in layers not exceeding 150 MM as directed and consolidating the same by through saturation with water ramming complte including the cost of supply of sand.(Payment to be made on measuremnet of finished quantity. Page no. 5 Item no. 4 A PWD BLDG</p>	9	m3	583.00	5247.00
7	<p>Labour for laying picked Jhama or 1st class brick edging,including cutting necessary trenches in all classes of soils or road crust, including re-filling the trenches with spoil and ramming the sides and backing with earthen bundh (600mm wide and 150mm average depth)all complite as per specification and direction of Engineer-in-charge, excluding the cost of bricks. (b)Brick edging on end (75mm wide and 254mm deep.)</p>	80.00	m3	71.40	5712.00

SAY

128752.14
128752

[Signature]
Assistant Engineer
P.W. Department
Baranagar Municipality

[Signature] 19/9/12
Chairman
Baranagar Municipality