



BARANAGAR MUNICIPALITY
87 DESHBANDHU ROAD KOLKATA 35


SPECIFIC PRICE SHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF
IMPROVEMENT OF PASSAGE AT 11/1 D.N. CHATTERJEE. ROAD.

ESTIMATE NO 048/PW/Dept./08

WARD NO-8

SL NO-13

SI No	Description of Items	Qty	Unit	Rate	Amount
1	Box cutting or filling in road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on burm to approx. gate and camber and rolling the sub grade with power roller to proper camber and grade as per direction and satisfaction of and grade as per direction and satisfaction of engineer in charge including uprooting and removings plants and jungles when and where necessary (a) upto 150 mm	10.5	SQM	9.60	100.80
2	125 mm thick brikwork with 1st class bricks in cement mortar 1:4 page no. 73 Item no, 29 PWD Bldg	6.30	m2	677.00	4265.10
3	10 Mm thick cement pluster with sand & cement morthor (4:1)with 1.5 Mm thick neat cement punningr page no. 319 Item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg	35.00	m2	124.29	4350.15
4	Cement concrete with graded jhamakua(30MM size) excluding shuttering a)1:3:6 proporton page no 33 item no. 4 A	0.65	m3	4766	3097.90
5	Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used) complets asper direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG	10.50	m2	340.00	3570.00



6	<p>Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containing designed quantity of cement per CU.m of weight concrete produced in computerised batching under controlled condition using approved super plasticized designed concrete mix following IS 10262 & IS 456 transporting the mix with segregation in transit mixture to work site depositing the mix on a platform erected for the purpose at required levels of concrete and the placing the mix in its final location of form work compacting & curing the same complete as per specification & direction of the Engineer-in-Charge including computerised batching plant transit mixture with all accessories vibrators etc inclusive of all other incidental charges in this connection complete but excluding cost of higher charge of platform and its supporting staging which would be paid through separate item (cement to be supplied by the manufacturer or supplier.)</p> <p>i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLDG</p>	4.95	m3	6207.16	30725.44
7	<p>Brick work with 1st class in cement mortar (1:6) in foundation and plinth page no. 69 Item no. 21(a) PWD Bldg</p>	1.57	CUM	4999.00	7848.43

SAY 53957.82
53958

[Signature]
Assistant Engineer
P.W. Department
Baranagar Municipality

[Signature] 19/9/12.
Chairman
Baranagar Municipality