

**BARANAGAR MUNICIPALITY**  
87 DESHBANDHU ROAD KOLKATA 35

SPECIFIC PRICE SHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF  
RECONSTRUCTION OF DRAIN AT RAIMOHAN BANERJEE ROAD




ESTIMATE NO 059/PW/Durb/16

WARD NO-16

SL NO-24

SI No	Description of Items	Qty	Unit	Rate	Amount
1	125 mm thick brickwork with 1st class bricks in cement mortar 1:4 page no. 73 item no. 29 PWD Bldg	81.00	m2	677.00	54837.00
2	10 Mm thick cement plaster with sand & cement mortar (4:1) with 1.5 Mm thick neat cement punningr page no. 319 item no. 2.(II)c and page no 323 item no. 8 PWD Bldg	453.60	m2	124.29	56377.94
3	Earth work in in excavation of foundation trenches or drains in all sorts of soil ( including mixed soil but excluding laterite or sanstone ) including removing spreading or stacking the spoils within a lead of 75 meters directed. The items includes necessary trimming the sides of trenches , labelling, dressing and ramming the bottom, the balling out the water as required complete. a) depth of excavation not exceeding not 1500MM. page no. 1 item no. 2A.	43.2	m3	73.77	3186.86
4	Cement concrete with graded Jhamakua(30MM size) excluding shuttering a) 1:3:6 proportion page no 33 item no. 4 A	10.12	m3	4766.00	48231.92
5	Single brick flat soiling packed Jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used ) complete as per direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG	135.00	m2	340.00	45900.00
6	Hires & labour charges for shuttering with centering & necessary staging up to 4 meter using approved stout props & thick hard wood planks of approved thickness with required bracing for concrete slabs beams & column lintels curved or straight including fixing & striking out after completion of works ( up to roof of ground floor) F) 25 Mm to 30 MM shuttering without staging in foundation Page no. 63 item no. 12 F PWD BLDG	11.00	m2	167.1	1838.10
7	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars stirrups , binders etc initial straightening and removal of loose rust ( if necessary ) cutting to requisite length , hooking and bending to correct safe, placing in proper position and binding with 16 gauge black annealed wire at every intersection complete as per drawing & direction. a) For work in foundation , basement & up to roof of ground floor / up to 4 m i) Tor steel / mild steel page no. 65 item no. 15 a I PWD BLDG	106.90	Kg.	54.23	5797.19
8	Dismantling all types of machinery excepting cement concrete plain or reinforced stacking servicable materials as slight & removing rubbish as directed within a lead of 75 M a) In ground floor including roof page no. 21 item no. 1a	8.10	m3	276.64	2240.78
9	Dismantling R.C. floor , roof, beams etc including cutting rods & removing rubbish as directed within a lead of 75 meter including stracking of steel burs	1.32	m3	1210	1597.20



10	Extra covered corresponding item of earth work for removing semi liquid mud or slushy earth by iron pans , buckets etc. ( This item is to be done with express approval of Engineer-In Charge) page no. 457 item no. 25 PWD Bldg.	18.90	m3	16.47	311.28
11	Removal of rubbish earth etc from the working site & disposal of the same beyond the compound in conformity with the Municipal / Corporation rules for such disposal loading into truck & cleaning the site in all respect as per direction of Enginner-In-Charge page no. 29 item no. 13 PWD BLDG	20.00	m3	143.99	2879.80
12	Brick work with 1st class in cement mortar (1:6) in foundation and plinth page no. 69 item no. 21(a) PWD Bldg	38.25	CUM	4999.00	191211.75
13	Ordinary cement concrete (Mix1:1.5:3) with graded stone chips ( 20mm nominal size) excluding shuttering and reinforcement if any in ground floor as per relevant IS code I) pakur varity p no 39 item no 7 (I)PWD BLDG	1.32	CUM	5675.32	7491.42

SAY

421901.25  
421901.00

*H.S.*  
Assistant Engineer  
P.W. Department  
Baranagar Municipality

*[Signature]* 19/9/12.  
Chairman  
Baranagar Municipality