


BARANAGAR MUNICIPALITY
87 DESHBANDHU ROAD KOLKATA 35

SPECIFIC PRICE SCHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF
IMP OF PASSAGE OF MONORANJAN NAGAR 'A'



ESTIMATE NO 062/PW/Dept/18

WARD NO - 18

SL NO - 27

SI No	Description of Items	Qty	Unit	Rate	Amount
1	Box cutting or filling in road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on burn to approx. gate and camber and rolling the sub grade with power roller to proper camber and grade as per direction and satisfaction of and grade as per direction and satisfaction of engineer in charge including uprooting and removing plants and jungles when and where necessary (a) upto 150 mm	540.00	SQM	9.60	5184.00
2	10 Mm thick cement plaster with sand & cement mortar (4:1) with 1.5 Mm thick neat cement punningr page no. 319 Item no. 2.(ii)c and page no 323 Item no. 8 PWD Bldg	667.00	m2	124.29	82901.43
3	Cement concrete with graded jhamakua(30MM size) excluding shuttering a)1:3:6 proporton page no 33 item no. 4 A	13.10	m3	4766.00	62434.60
4	Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used) complet asper direction a) single brick flat soiling thickness 75 MM page no. 393 Item no. 1 A, PWD BLDG	714.80	m2	340.00	243032.00
	Brick work with 1st class in cement mortar (1:6) in foundation and plinth page no. 69 Item no. 21(a) PWD Bldg	69.00	CUM	4999.00	344931.00
5	Earth work in in excavation of foundation trenches or drains in all sorts of soil (including mixed soil but excluding laterite or sanstone) including removing spreading or stacking the spoils within a lead of 75 meters directed. The items includes necessary trimming the sides of trenches , labelling, dressing and ramming the bottom, the bailing out the water as required complete. a) depth of excavation not exceeding not 1500MM. page no. 1 Item no. 2A.	78.66	m3	73.77	5802.75
6	Labour for laying picked Jhama or 1st class brick edging including cutting necessary trenches in all classes of soils or road crust, including re-filling the trenches with spoil and ramming the sides and backing with earthen bundh (600mm wide and 150mm average depth)all complete as per specification and direction of Engineer-in-charge, excluding the cost of bricks. (b)Brick edging on end (75mm wide and 254mm deep.)	360.00	M	71.40	25704.00
7	Removal of rubbish earth etc from the working site & disposal of the same beyond the compound in conformity with the Municipal / Corporation rules for such disposal loading into truck & cleaning the site in all respect as per direction of Enginner-in-Charge page no. 29 Item no. 13 PWD BLDG	80.00	m3	143.99	11519.20
8	Ordinary cement concrete (Mix1:1.5:3) with graded stone chips (20mm nominal size) excluding shuttering and reinforcement if any in ground floor as per relevant IS code i) pakur varity p no 39 item no 7 (i)PWD BLDG	56.25	CUM	5675.32	319236.75 1100745.73 1100746.00

SAY

[Signature]
Assistant Engineer
P.W. Department
Baranagar Municipality

[Signature] 19/9/12
Chairman
Baranagar Municipality