

BARANAGAR MUNICIPALITY

87 DESH BANDHU ROAD(E) KOLKATA-35



SPECIFIC PRICE SCHEDULE OF POTABLE ITEMS WITH RATES AND APPROXIMATE QUANTITIES
FOR THE WORK OF IMPROVEMENT OF PASSAGE OF MONDAL PARA LANE NEAR
PRES. NO-28, AS PER PWD SCHEDULE AUG-2010 BUILDING AND ROAD 2008-2009
AND CORIGENDUM APRIL 2012


ESTIMATE NO 066/PW/Dept/20

WARD NO-20

SL NO:-31

SI No	Description of Items	Qty	Unit	Rate	Amount
1	Filling in foundation or plinth by silver sand in layers not exceeding 150 MM as directed and consolidating the same by through saturation with water ramming complete including the cost of supply of sand. (Payment to be made on measurement of finished quantity. Page no. 5 Item no. 4 A PWD BLDG	1	M3	583.00	583.00
2	Box cutting or filling in road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on berm to approx. gate and camber and rolling the sub grade with power roller to proper camber and grade as per direction and satisfaction of and grade as per direction and satisfaction of engineer in charge including uprooting and removing plants and jungles when and where necessary (a) upto 150 mm	75.90	m2	7.70	584.43
3	Brick work with 1 st class bricks in cement mortar 6:1 a in foundation and plinth page-69 item 22 a	1.09	M3	4999.00	5448.91
4	10 Mm thick cement plaster with sand & cement mortar (4:1) with 1.5 Mm thick neat cement punningr page no. 319 Item no. 2.(ii)c and page no 323 item no. 8 PWD Bldg	12.36	m2	124.29	1536.22
5	Earth work in in excavation of foundation trenches or drains in all sorts of soil (including mixed soil but excluding laterite or sanstone) including removing spreading or stacking the spoils within a lead of 75 meters directed. The items includes necessary trimming the sides of trenches , labelling, dressing and ramming the bottom, the bailing out the water as required complete. a) depth of excavation not exceeding not 1500MM. page no. 1 item no. 2A.	0.35	m3	73.77	25.82
6	Cement concrete with graded jhamakua(30MM size) excluding shuttering a)1:3:6 proportion page no 33 item no. 4 A	0.04	m3	4766.00	190.64

BARANAGAR MUNICIPALITY
87 DESH BANDHU ROAD(E) KOLKATA-35



7	<p>Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containing designed quantity of cement per CU.m of weight concrete produced in computerised batching under controlled condition using approved super plastisized designed concrete mix following IS 10262 & IS 456 transporting the mix with egutation in trabsit mixture to work site depositing the mix on aplatform erected for the purpose at required lebe;s of concreteing and the placing the mix in its final locatio0n of form work compacting & curibg the same complete as per specification & direction of the Engineer --in -Charge including computerised batching plnat transit mixture with all assesories vibratorsr etc inclusive of all other incidental charges in this connection complate but excluding cost of higher charge of platform and its supporting staging which would be paid through seperate item (cement to be suplied by the manufactures or supplier .)</p> <p>i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLDG</p>	5.69	m3	6207.16	35318.74
8	<p>Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used) complets asper direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG</p>	76.48	m2	340	26003.20
9	<p>Removal of rubbish earth etc from the working site & disposal of the same beyond the compound in confermity with the Municipal / Corporation rules for such disposal loading into truck & cleaning the site in all respect as per direction of Enginner-in-Charge page no. 29 Item no. 13 PWD BLDG</p>	5.00	m3	143.99	719.95

Total Rs. 70410.91

Say Rs.70411.00

For
Assistant Engineer
P.W. Department
Baranagar Municipality

Chairman
Chairman
Baranagar Municipality
19/9/12.