

BARANAGAR MUNICIPALITY
87 DESH BANDHU ROAD(E) KOLKATA-35



SPECIFIC PRICE SCHEDULE OF POTABLE ITEMS WITH RATES AND APPROXIMATE QUANTITY
FOR THE WORK OF IMPROVEMENT OF PASSAGE OF K.C.GHOSH ROAD FROM
PRES. NO-15/1 TO 35/5,, AS PER PWD SCHEDULE AUG-2010 BUILDING AND
ROAD 2008-2009AND CORIGENDUM APRIL 2012

ESTIMATE NO 067/PW/Dept/21 WARD NO-21 SL NO:-32

SI No	Description of Items	Qty	Unit	Rate	Amount
1	Labour for taking out old solling edging including removing debris a) Single brick flat solling page no.397 item no. 6(a)	204	m2	6.07	1238.28
2	Labour for laying solling with departmental bricks including including carriage of departmental bricks within a lead of 150 m preparation of bed as necessary with bricks joint properly field inand packed with bricks joints properly field in and packed with local sand or powder earth and including necessary quassion of similar material below the solling (and in between layers when more than one layer in use) the item included the cost of optaining local sand of powder earth a) single brick flat solling (thickness 75 mm)	150.51	m2	22.25	3348.85
3	Laying picked jhama or 1st class brick edgging, including cutting necssary trenches in all class of soil or road crust including refilling the treches with spoil and raming the side and baking with earthening bank (600 mm wide and 150 mm average depth) all complete as per specification and direction in engineer in charge b) brick edging on end (75mm wide and 254 mm depth p-262, I-10 b)	41.90	mt	71.4	2991.66
4	Brick work with 1 st class bricks in cement mortar 6:1 a in foundation and plinth page-69 item 22 a	0.75	M3	4999.00	3749.25
5	10 mm thick cement plaster with sand & cement morthor (4:1)with 1.5 Mm thick neat cement punningr page no. 319 Item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg	3.00	m2	124.29	372.87

BARANAGAR MUNICIPALITY
87 DESH BANDHU ROAD(E) KOLKATA-35


6	<p>Supplying bending and binding and laying in position steel reinforcement of different dimension in cement concrete work i.e R.C.C. P.S.C etc. of different components in foundation substructure and in super structure etc. including straightning strengthening of spoils bars, removal of loose rust if any, cutting to requisite length bending, binding with annealed wire not less than 1 mm in size and conforming to I.S. 280 at every intersection hooked and bent to correct shape and placed on forms etc. including cost of backed anailed wire and cost of loding , unloding, carage of all steels materials from departmental godown complete as per drawing and direction of ingineer in charge (a) for M.S. rounds/ torque steel page no-214 item no-19 a</p>	28.52	kg	54.23	1546.64
7	<p>Earth work in in excavation of foundation trenchesor drains in all sorts of soil (including mixed soil but excluding laterrite or sanstone) including removing spreading or stacking the spoils within a lead of 75 meteras directed. The items includes necessary trimmiing the sides of trenchs , labelling, dressing and ramming the bottom, the bailing out the water as required complete. a) depth of excavation not exceeding not 1500MM. page no. 1 item no. 2A.</p>	10.00	m3	73.77	737.70

BARANAGAR MUNICIPALITY
87 DESH BANDHU ROAD(E) KOLKATA-35



8	<p>Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containing designed quantity of cement per CU.m of weight concrete produced in computerised batching under controlled condition using approved super plasticized designed concrete mix following IS 10262 & IS 456 transporting the mix with segregation in transit mixture to work site depositing the mix on a platform erected for the purpose at required levels of concrete and the placing the mix in its final location of form work compacting & curing the same complete as per specification & direction of the Engineer-in-Charge including computerised batching plant transit mixture with all accessories vibrators etc inclusive of all other incidental charges in this connection complete but excluding cost of higher charge of platform and its supporting staging which would be paid through separate item (cement to be supplied by the manufacturer or supplier .)</p> <p>i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLDG</p>	23.83	m3	6207.16	147916.62
9	<p>Single brick flat soiling packed jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used) complete as per direction</p> <p>a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG</p>	125.4	m2	340	42636.00
10	<p>centering & necessary staging up to 4 meter using approved stout props & thick hard wood planks of approved thickness with required bracing for concrete slabs beams & column lintels curved or straight including fixing & striking out after completion of works (up to roof of ground floor)</p> <p>F) 25 Mm to 30 MM shuttering without staging in foundation Page no. 63 item no. 12 F PWD BLDG</p>	2.66	m2	167.1	444.49

BARANAGAR MUNICIPALITY
87 DESH BANDHU ROAD(E) KOLKATA-35



11	<p>Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containing designed quantity of cement per CU.m of weight concrete produced in computerised batching under controlled condition using approved super plasticized designed concrete mix following IS 10262 & IS 456 transporting the mix with segregation in transit mixture to work site depositing the mix on a platform erected for the purpose at required levels of concrete and the placing the mix in its final location of form work compacting & curing the same complete as per specification & direction of the Engineer-in-Charge including computerised batching plant transit mixture with all accessories vibrators etc inclusive of all other incidental charges in this connection complete but excluding cost of higher charge of platform and its supporting staging which would be paid through separate item (cement to be supplied by the manufacturer or supplier.)</p> <p>i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLDG</p>				
12	<p>Removal of rubbish earth etc from the working site & disposal of the same beyond the compound in conformity with the Municipal / Corporation rules for such disposal loading into truck & cleaning the site in all respects as per direction of Engineer-in-Charge page no. 29 Item no. 13 PWD BLDG</p>	10.00	m3	143.99	1439.90
		Total Rs.		206422.25	

Say Rs.206422.00


Assistant Engineer
P.W. Department
Baranagar Municipality


Chairman
Baranagar Municipality