

BARANAGAR MUNICIPALITY
87 DESHBANDHU ROAD KOLKATA 35

SPECIFIC PRICE SCHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF
IMPROVEMENT OF PASSAGE OF DAS PARA ROAD FROM PRE NO 56 MOIRA DANGA ROAD




ESTIMATE NO 074/PW/Dept/26

WARD NO - 25

SL NO - 39

SI No	Description of Items	Qty	Unit	Rate	Amount
1	Labour for taking out old soiling edging including removing debris a) Single brick flat soiling page no.397 item no. 6(a)	484.50	m2	6.07	2940.92
2	Labour for taking out old soiling edging including removing debris b) Double brick flat soiling page no.397 item no. 6(b)	584.00	m2	8.93	5215.12
3	Brick work with 1st class brick with cement mortar (1:6) page no.69 item no. 22A	27.14	m3	4999.00	135672.86
4	125 ML thick brikwork with 1st class bricks in cement mortar 1:4 page no. 73 item no. 29 PWD Bldg	76.05	m2	677.00	51485.85
5	10 Mm thick cement plaster with sand & cement mortar (4:1)with 1.5 Mm thick neat cement punningr page no. 319 item no. 2.(ii)c) and page no 323 item no. 8 PWD Bldg	361.48	m2	124.29	44928.35
6	Earth work in in excavation of foundation trenches or drains in all sorts of soil (including mixed soil but excluding laterite or sanstone) including removing spreading or stacking the spoils within a lead of 75 meters directed. The items includes necessary trimmiing the sides of trenches , labelling, dressing and ramming the bottom, the bailing out the water as required complete. a) depth of excavation not exceeding not 1500MM. page no. 1 item no. 2A.	92.62	m3	73.77	6832.58
7	Box cutting or filling in road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on burn to approx. gate and camber and rolling the sub grade with power roller to proper camber and grade as per direction and satisfaction of and grade as per direction and satisfaction of engineer in charge including uprooting and removings plants and jungles when and where necessary (a) upto 150 mm	974.70	SQM	9.60	9357.12
8	Cement concrete with graded jhamakua(30MM size) excluding shuttering a)1:3:6 proporton page no 33 item no. 4 A	2.63	m3	4766.00	12534.58
9	Labour for laying soiling with departmental bricks including including carriage of departmental bricks within a lead of 150 m preparation of bed as necessary with bricks joint properly field inand packed with bricks joints properly field in and packed with local sand or powder earth and including necessary quassion of similar material below the soiling (and in between layers when more than one layer in use) the item included the cost of optaining local sand of powder earth a) single brick flat soiling (thickness 75 mm)	391.59	m2	25.18	9860.24
10	Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used) complets asper direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG	799.75	m2	340.00	271915.00



11	Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containing designed quantity of cement per CU.m of weight concrete produced in computerised batching under controlled condition using approved super plasticized designing concrete mix following IS 10262 & IS 456 transporting the mix with egutation in trabsit mixture to work site depositing the mix on aplatform erected for the purpose at required lebe;s of concreteing and the placing the mix in its final locatioon of form work compacting & curibg the same complete as per specification & direction of the Engineer -in -Charge including computerised batching pinat transit mixture with all assesories vibrators etc inclusive of all other incidental charges in this connection complete but excluding cost of higher charge of platform and its supporting staging which would be paid through separate item (cement to be supplied by the manufactures or supplier .) i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLDG	94.1	m3	6207.16	584093.76
12	Hires & labour chargesfor shuttering wuth centering & necessary staging up to 4 meter using approved stout props & thick hard wood planks of approved thickness with required bracing for concrete slabs beams & column lintels curved or straight including fixing & striking out after completion of works (up to roof of ground floor) F) 25 Mm to 30 MM shuttering without staging in foundation Page no. 63 item no. 12 F PWD BLDG	124.25	m2	167.10	20762.18
13	Dismelting all types of machinery excepting cement concrete plain or reinforced stacking servicable materials as sight & removing rubbish as directed within a lead of 75 M a) In ground floor including roof page no. 21 item no. 1a	3.24	m3	276.64	896.31
14	Extra overed correspnding item of earth work for removing semi liquide mud or slushy earth by iron pans , buckets etc. (This item is to be done with express approval of Engineer-in Charge) page no. 457 item no. 25 PWD Bldg.	11.38	m3	16.48	187.54
15	Removal of rubbish earth etc from the working site & disposal of the same beyond the compound in conformity with the Municipal / Corporation rules for such disposal loading into truck & cleaning the site in all respect as per direction of Engineer-in-Charge page no. 29 item no. 13 PWD BLDG	74.93	m3	143.99	10789.17
16	Filling in foundation or plinth by silver sand in layers not exceeding 150 MM as directed and consolidating the same by through saturation with water ramming complete including the cost of supply of sand.(Payment to be made on measurement of finished quantity. Page no. 5 Item no. 4 A PWD BLDG	79.68	m3	583.00	46453.44
17	Labour for laying picked Jhama or 1st class brick edging,including cutting necessary trenches in all classes of soils or road crust, including re-filling the trenches with spoil and ramming the sides and backing with earthen bundh (600mm wide and 150mm average depth)all complete as per specification and direction of Engineer-in-charge, excluding the cost of bricks. (b)Brick edging on end (75mm wide and 254mm deep.)	481.00	M	71.40	34343.40
18	Earth work in filling in foundation trenches or plinth with good earth in layers not exceeding 150 mm including watering and ramming etc layer by layer complete. (payment to be made on the basis of measurement of finished quantity ofwork) (a) with earth obtained from excavation of foundation	17.69	m3	47.60	842.04
19	Extra for rusticated plaster within (over rate of corresponding item of plaster)	130.13	m2	11.30	1470.469
					1250580.92
					1250581.00

SAY

[Signature]
Assistant Engineer
P.W. Department
Baranagar Municipality

[Signature] 19/9/12
Chairman
Baranagar Municipality