

**BARANAGAR MUNICIPALITY**  
87 DESHBANDHU ROAD KOLKATA 35


SPECIFIC PRICE SHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF  
construction of drain from culvert at MS BATAKRISHNA MOITRA school to B T ROAD (NORTHERN SIDE)

ESTIMATE NO 075/PW/D-18/27

WARD NO - 27

SL NO - 40


SI No	Description of Items	Qty	Unit	Rate	Amount
1	125 mm thick brikwork with 1st class bricks in cement mortar 1:4 page no. 73 Item no, 29 PWD Bldg	41.25	m2	677.00	27926.25
2	10 Mm thick cement plaster with sand & cement morther (4:1)with 1.5 Mm thick neat cement punningr page no. 319 Item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg	144.75	m2	124.29	17990.98
3	Earth work in in excavation of foundation trenchesor drains in all sorts of soil ( including mixed soil but excluding laterrite or sanstone ) including removing spreading or stacking the spoils within a lead of 75 meters directed. The items includes necessary trimmiling the sides of trenches , labelling, dressing and ramming the bottom, the bailing out the water as required complete. a) depth of excavation not exceeding not 1500MM. page no. 1 item no. 2A.	28.63	m3	73.77	2112.04
4	Cement concrete with graded jhamakua(30MM size) excluding shuttering a)1:3:6 proporton page no 33 item no. 4 A	4.67	m3	4766.00	22257.22
5	Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used ) complets asper direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG	62.25	m2	340.00	21165.00
6	Dismelting all types of machinery excepting cement concrete plain or reinforced stacking servicable materials as sight & removing rubbish as directed within a lead of 75 M a) In ground floor including roof page no. 21 item no. 1a	5.05	CUM	276.64	1397.03
7	Dismelting R.C. floor , roof, beams etc including cutting rods & removing rubbish as directed within a lead of 75 meter including stracking of steel burs	3.00	m3	1210.00	3630.00



8	Removal of rubbish earth etc from the working site & disposal of the same beyond the compound in conformity with the Municipal / Corporation rules for such disposal loading into truck & cleaning the site in all respect as per direction of Enginner-in-Charge page no. 29 Item no. 13 PWD BLDG	40.00	m3	143.99	5759.60
9	Brick work with 1st class in cement mortar (1:6) in foundation and plinth page no. 69 Item no, 21(a) PWD Bldg	10.31	CUM	4999.00	51539.69
SAY					153777.80 153778.00

  
 Assistant Engineer  
 P.W. Department  
 Baranagar Municipality

  
 Chairman  
 Baranagar Municipality  
 19/9/12



8	Removal of rubbish earth etc from the working site & disposal of the same beyond the compound in conformity with the Municipal / Corporation rules for such disposal loading into truck & cleaning the site in all respect as per direction of Engineer-in-Charge page no. 29 Item no. 13 PWD BLDG	40.00	m3	143.99	5759.60
9	Brick work with 1st class in cement mortar (1:6) in foundation and plinth page no. 69 Item no. 21(a) PWD Bldg	10.31	CUM	4999.00	51539.69
				SAY	153777.80
					153778.00

~~#08~~  
Assistant Engineer  
P.W. Department  
Baranagar Municipality

*[Signature]* 19/9/12.  
Chairman  
Baranagar Municipality

