




**BARANAGAR MUNICIPALITY**  
87 DESHBANDHU ROAD KOLKATA 35

SPECIFIC PRICE SHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF  
IMP OF PASSAGE AT 108/1/1 GOPAL LAL TAGORE ROAD

ESTIMATE NO	WARD NO - 27	SL NO - 41			
SI No	Description of Items	Qty	Unit	Rate	Amount
1	Box cutting or filling in road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on burm to approx. gate and camber and rolling the sub grade with power roller to proper camber and grade as per direction and satisfaction of and grade as per direction and satisfaction of engineer in charge including uprooting and removings plants and jungles when and where necessary (a) upto 150 mm	50.00	SQM	9.60	480.00
2	125 mm thick brikwork with 1st class bricks in cement mortar 1:4 page no. 73 item no, 29 PWD Bldg	8.75	m2	677.00	5923.75
3	10 Mm thick cement pluster with sand & cement morthor (4:1)with 1.5 Mm thick neat cement punningr page no. 319 item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg	32.50	m2	124.29	4039.43
					0.00
4	Cement concrete with graded Jhamakua(30MM size) excluding shuttering a)1:3:6 proporton page no 33 item no. 4 A	1.26	m3	4766	6005.16
5	Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used ) complets asper direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG	66.88	m2	340.00	22739.20
6	Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containg designigned quantity of cement par CU.m of weight concrete produced in computerised batchinng under controlled condition using approved super plastisized designing concrete mix followibg IS 10262 & IS 456 transporting the mix with egutation in trabsit mixture to work site depositing the mix on aplatform erected for the purpose at required lebe;s of concreteing and the placing the mix in its final locatioOn of form work compacting & curibg the same complete as per specification & direction of the Engineer --in - Charge including computerised batching pinat transit mixture witi all assesories vibratorsr etc inclusive of all other incidental charges in this connection complte but excluding cost of higher charge of platform and its supporting staging which would be paid through separete item ( cement to be suplied by the manufactures or supplier .) i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLDG	3.86	m3	6207.16	23959.64
7	Hires & labour chargesfor shuttering wuth centering & necessary staging up to 4 meter using approved stout props & thick hard wood planks of approved thckness with required bracing for concrete slabs beams & column lintels curved or straight including fixing & striking out after completion of works ( up to roof of ground floor) F) 25 Mm to 30 MM shuttering without staging in foundation Page no. 63 item no. 12 F PWD BLDG	1.72	m2	167.10	287.41

ESTIMATE NO 076/PW/Dkt.127



8	<p>Rnforcement for reinforced concrete work in all sorts of structures including distribution bars stirrups , binders etc initial straightening and removal of loose rust ( if necessary )cuttong to requisute length , hooking and bending to corrcet safe, placing in proper position and binding with 16 gauge black annealed wire at every intersection complte as pere drawing &amp; direction.</p> <p>a) For work in foundation , basemnet &amp; up to roof of ground flor / up nto 4 m</p> <p>i) Tor steel / mild steel</p> <p>page no. 65 item no. 15 a i PWD BLDG</p>	20.69 Kg.		54.23	1122.02
9	<p>Brick work with ist class in cement mortar (1:6) in foundation and plinth page no. 69 Item no, 21(a) PWD Bldg</p>	1.875 CUM		4999.00	9373.13
10	<p>Earth work in in excavation of foundation trenchesor drains in all sorts of soil ( including mixed soil but excluding laterrite or sanstone ) Including removing spreading or stacking the spoils within a lead of 75 meteras directed. The items includes necessary trimmiing the sides of trenches , labelling, dressing and ramming the bottom, the bailing out the water as required complete.</p> <p>a) depth of excavation not exceeding not 1500MM.</p> <p>page no. 1 item no. 2A.</p>	7.53	m3	73.77	555.49

74485.22

SAY

74485.00

*H. J. K.*  
 Assistant Engineer  
 P.W. Department  
 Baranagar Municipality

*[Signature]* 19/9/12  
 Chairman  
 Baranagar Municipality