


BARANAGAR MUNICIPALITY
87 DESHBANDHU ROAD KOLKATA 35




SPECIFIC PRICE SCHEDULE OF PORTABLE ITEMS WITH APPROXIMATE QUANTITY AND RATES FOR THE WORK OF
IMP OF PASSAGE STARTING FROM PRE 129 TO 133 M N K ROAD (S)

ESTIMATE NO 078/PW/Dept/29

WARD NO - 29

SL NO - 43

| SI No | Description of Items | Qty | Unit | Rate | Amount |
|-------|--|--------|------|---------|----------|
| 1 | Labour for taking out old soiling edging including removing debris a) Single brick flat soiling page no.397 item no. 6(a) | 192.00 | m2 | 6.07 | 1165.44 |
| 2 | 125 mm thick brickwork with 1st class bricks in cement mortar 1:4 page no. 73 Item no, 29 PWD Bldg | 18.00 | m2 | 677.00 | 12186.00 |
| 3 | 10 Mm thick cement plaster with sand & cement mortar (4:1)with 1.5 Mm thick neat cement punningr page no. 319 item no, 2.(ii)c) and page no 323 item no. 8 PWD Bldg | 75.00 | m2 | 124.29 | 9321.75 |
| 4 | Single brick flat soiling pcked jhama bricks including preparation of bed as necessary with brick joints properly filled in and in and packed with powdered earth and including necessary cushion of similar material below the soiling (and in between layers when more than one layer is used) complet asper direction a) single brick flat soiling thickness 75 MM page no. 393 item no. 1 A, PWD BLDG | 76.80 | m2 | 340.00 | 26112.00 |
| 5 | Brick work with 1st class in cement mortar (1:6) in foundation and plinth page no. 69 Item no, 21(a) PWD Bldg | 6.30 | CUM | 4999.00 | 31493.70 |
| 6 | Filling in foundation or plinth by silver sand in layers not exceeding 150 MM as directed and consolidating the same by through saturation with water ramming complete including the cost of supply of sand.(Payment to be made on measurement of finished quantity. Page no. 5 Item no. 4 A PWD BLDG | 14.40 | m3 | 583.00 | 8395.20 |
| 7 | Labour for laying soiling with departmental bricks including including carriage of departmental bricks within a lead of 150 m preparation of bed as necessary with bricks joint properly field in and packed with bricks joints properly field in and packed with local sand or powder earth and including necessary quassion of similar material below the soiling (and in between layers when more than one layer in use) the item included the cost of optaining local sand of powder earth a) single brick flat soiling (thickness 75 mm) | 115.20 | m2 | 25.18 | 2900.74 |



| | | | | |
|--|-------|----|---------|------------------------------------|
| 8 Supplying ready mix concrete of capital M20 Grade with well graded stone chips of 20MM nominal size containing designed quantity of cement per CU.m of weight concrete produced in computerised batching under controlled condition using approved super plasticized designing concrete mix following IS 10262 & IS 456 transporting the mix with egutation in trabsit mixture to work site depositing the mix on aplatform erected for the purpose at required lebe;s of concreteing and the placing the mix in its final locatio0n of form work compacting & curibg the same complete as per specification & direction of the Engineer --in -Charge including computerised batching plnat transit mixture with all assesories vibrators etc inclusive of all other incidental charges in this connection complate but excluding cost of higher charge of platform and its supporting staging which would be paid through separate item (cement to be supplied by the manufactures or supplier .) i) Without approved concrete pump ii) With approved concrete pump page no. 51 item no. 9 B (a) i 7 ii PWD BLDG | 14.40 | m3 | 6207.16 | 89383.10 180957.93 180958.00 |
|--|-------|----|---------|------------------------------------|

SAY

H. S. S.
Assistant Engineer
P.W. Department
Baranagar Municipality

[Signature] 19/9/12
Chairman
Baranagar Municipality