

BARANAGAR MUNICIPALITY

TENDER NOTICE NO: 75/PW/15-16
No..... Date: 4/1/15.....

M/s.....

SEALED Tender is invited and will be received by the **Chairman up to 3 P.M of 11.01.2016** the following work as per terms and condition given below.

The Tender should be addressed to the Chairman, superscripted for” **REPAIRING OF DRAIN FROM PRE.NO. 50/1 ,M.N.K ROAD TO 120/1 M.N.K ROAD , AT WARD NO -06 UNDER THIS MUNICIPALITY. ”**

LAST DATE OF DROPPING- **11.01.2016**

SL. NO	WORK DESCRIPTION	TENDER AMOUNT Rs.	STIPULATED PERIOD
01.	” REPAIRING OF DRAIN FROM PRE. NO. 50/1 ,M.N.K ROAD TO 120/1 M.N.K ROAD , AT WARD NO -06 “	4,80,744.00	45 Days.

4/1/16
E.O./F.O.

4/1/16
CHAIRMAN.

TERMS & CONDITION

- 1) Tenders to be submitted in the prescribed tender Form which will have to be obtained from the Municipality at a prescribed cost or Demand draft of Rs.200/- attached with the form downloaded from our website www.baranagarmunicipality.org.
- 2) **Tenderer must be registered under “ West Bengal Building and other Contribution Welfare Cess ,E.P.F & E.S.I Act. otherwise it will not be treated as valid.**
- 3) **Earnest Money of 2 % of the estimated cost** should be deposited along with the tender.
- 4) The stipulated date for commence / completion of work as per work order issued will have to strictly followed.
- 5) Successful Tenderer (work above Rs.5000/-) shall have to execute a formal Agreement with the Municipality within a week from the date of intimation of the acceptance of his Tender at his own cost & risk.
- 6) The Chairman also reserves the right of accepting of canceling any Tender without assigning any reason thereof.
- 6) If the successful tenderer fails to complete the job within the specified time, a fine of at a stipulated rate(Rs.25/- per day)as fixed by the Municipal Authority will be levied.
- 7) **All Tenders are to be drop in the “Tender dropping Box” kept in the Chairman’s room otherwise it will not be treated as valid.**

Year-

Page no-

BARANAGAR MUNICIPALITY

ESTIMATE FOR REPAIRING OF DRAIN FROM PRE. NO 50/1 M.N.K ROAD
TO 120/1 M.N.K.ROAD AT WARD NO -06

Estimate no

Tender no

SL	DESCRIPTION OF WORKS	QUANTITY	UNIT	RATE	AMOUNT
1.	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. P- 7,IT 1	40.5 M3	M3	451.00	18,265.50
2)	Single brick flat soling of picked jhama bricks including rramming and dressing bed to proper level and filling joints with local sand. p-11,it-1	180 M2	M2	377=00	67,860.00
3)	Ordinary mix cement concrete (1:1.5:3)with graded stone chips (20mm nominal size) excluding shuttering and reinforcement if any,in ground floor as per relevant IS codes (i) Pakur varity p-14,it-7/i	18.9 M3	CuM	5389=00	1,01,852.10

4)	Brick work in first class bricks in cement mortar(1:6) (a)in foundation and plinth p-29,it-22/a	41 M3	M3	5719=00	2,34,479.00
5)	125mm thick brick work with 1 st class bricks in cement mortar(1:4)in ground floor p-31,it-29	1.2M2	M2	783=00	939.60
6)	Plaster(to wall,floor,celling etc)with sand and cement mortar including rounding off or chamfering comes as directed and raking out joints including throating,nosing and dripcourse,scaffolding/staging where necessary(ground floor).[Excluding cost of chepping over concrete surface]With (1:4) cement mortar 15mm thick p-151,it-2/ii/b	252 m2	M2	176.00	44,352.00
7)	Net cement punning about 1.5mmthick in wall,dado,windowsill,floor etcp-152,it-8	342 m2	M2	38.00	12,996.00

Total = 4,80,744.00

Add 3% Contingency of above = 14,422.00

Add 1% Cess of above = 4,807.00

Gross Total = 4,99,973.00

(Four Lakh Ninety Nine Thousand Nine hundred Seventy Three Only)


19/12/15


19/12/15