

BARANAGAR MUNICIPALITY

TENDER NOTICE NO: 022/PW/15-16

No. PW/022/1-15-16 Date 5/8/15

M/s.....

SEALED Tender is invited and will be received by the **Chairman up to 3 P.M of 17.08.2015** for the following work as per terms and condition given below.

The Tender should be addressed to the Chairman, superscripted for " **RENOVATION OF TAX COLLECTION CENTRE AT WARD NO-15 UNDER THIS MUNICIPALITY.** "

LAST DATE OF DROPPING- **17.08.2015**

SL. NO	WORK DESCRIPTION	TENDER AMOUNT Rs.	STIPULATED PERIOD
01.	RENOVATION OF TAX COLLECTION CENTRE AT WARD NO-15 UNDER THIS MUNICIPALITY.	88,613.00	As per Office Direction.

16/08/15
E.O./F.O..

Chairman
CHAIRMAN.

TERMS & CONDITION

- 1) Tenders to be submitted in the prescribed tender Form which will have to be obtained from the Municipality at a prescribed cost or Demand draft of Rs.200/- attached with the form downloaded from our website www.baranagarmunicipality.org.
- 2) **Tenderer must be registered under " West Bengal Building and other Contribution Welfare Cess ,E.P.F & E.S.I Act. otherwise it will not be treated as valid.**
- 3) Earnest Money of 2 % of the estimated cost should be deposited along with the tender.
- 4) The stipulated date for commence / completion of work as per work order issued will have to strictly followed.
- 5) Successful Tenderer (work above Rs.5000/-) shall have to execute a formal Agreement with the Municipality within a week from the date of intimation of the acceptance of his Tender at his own cost & risk.
- 6) The Chairman also reserves the right of accepting of canceling any Tender without assigning any reason thereof.
- 6) If the successful tenderer fails to complete the job within the specified time, a fine of at a stipulated rate(Rs.25/- per day)as fixed by the Municipal Authority will be levied.
- 7) **All Tenders are to be drop in the "Tender dropping Box" kept in the Chairman's room otherwise it will not be treated as valid.**

Estimate No.

Tender No.

Order No.

BARANAGAR MUNICIPALITY

Estimate for Renovation of Tax Collection Centre at Ward - 15

DESCRIPTION	No.	Measurement			Content and Total	Unit	Rate	Per	Amount		Remarks
		L	B	H					Rs.	P.	
1) Stripping of worn out plaster etc. ceiling	0.80	4.60	3.05	-	11.22						
Inside wall	0.80	2(4.60+3.05)			36.72						
Outside wall	0.80	2(5.20+3.60)			49.28						
					97.22	m	19.00	m			1247.18
2) Plaster with (1:4) 20mm											
Inside wall	2	(4.60+3.05)	1.8	3	36.72						
Outside wall	0.80	2(5.20+3.60)		3.50	49.28						
					86.00	m	206.00	m			17716.00
3) Plaster with (1:4) ceiling	10mm	0.80	4.60	3.05	-	11.22	m	140.00	m		1570.8
4) Heat Cement flooring	1	2.00	0.30	-	6.00	m	38.00	m			228.0
5) Dismantling Masonry	20	0.40	0.40	0.30	2.94	m	45.00	m			1325.94
6) Brick work (1:6)	1	2.00	1.00	1.00	2.00	m	59.43	m			11886.00
7) 125mm th. Brick work (1:4)	1	5.00	1.00	-	5.00	m	783	m			3915.00
8) Artificial Stone in floor (1:2:4) 35mm	1	4.00	3.00	-	12.00	m	372.00	m			4464.00
					c/o		TOTAL RS.				42952.92

Date

Sanctioned
Chairman
Baranagar Municipality

Ruppes
BARANAGAR MUNICIPALITY

S. A. ENGINEER / ESTIMATOR

Asst. Engineer
Public Works Dept

BARANAGAR MUNICIPALITY

Estimate for

DESCRIPTION	No.	Measurement			Content and Total	Unit	Rate	Per	Amount		Remarks
		L	B	H					Rs.	P.	
9) Stationary Cement Concrete (1:1.5:3)	1	4	3	0.10	1.20	m	5389	m	6466.8		
10) Wood work in body of window frame fitted & fixed in position complete including protective coat of painting at the contact surface of the frame with Sal local @ 15872.79/m ²	1	1.20	0.075	0.075	0.03						
	2	0.90	0.075	0.075	0.01	3					
					0.04	m	89279	m ²	3571.16		
11) Supplying fitting & fixing MS clamp for door & window frame 40mm X 6mm; 200mm length	12	-	-	-	12.00	pc	28.00	pc	336		
12) Iron Bolt Nippers 75 X 77 X 1.70mm	18	-	-	-	18.00	pc	37.00	pc	612		
13) Iron Socked Bolt 150mm long X 10mm	-	-	-	-	6.00	pc	71.00	pc	426		
14) Iron door pulling 50mm dia	-	-	-	-	6.00	pc	19.00	Each	114		
15) Styles and rails of window shutter fitted & fixed complete 37.5mm Th Shutter Gama HD wood	8	1.20	0.075	-	0.72						
	6	0.90	0.075	-	0.675						
					1.395	m	2656.00	m	3705	12	

Date

Sanctioned
Chairman
Baranagar Municipality

Ruppes C/O TOTAL RS. 58124 00

BARANAGAR MUNICIPALITY

The

S. A. ENGINEER / ESTIMATOR

Asst. Engineer
Public Works Dept.

BARANAGAR MUNICIPALITY

Estimate for

DESCRIPTION	No.	Measurement			Content and Total	Unit	Rate	Per	Amount		Remarks
		L	B	H					Rs.	P.	
16) Panel (made of single plank) of window shutter							B/F	=	52184	68	
16 months panel of 30 cm to 45 cm Gannay	8	0.235	0.50	-	1.14	m ²	1278.00	m	1789	20	
17) Earth work in excavation	1	1.60	1.95	0.30	6.96	m ³	120.47	m ³	838	47	
18) Removal of rubble					6.96	m ³	168.00	m ³	1169	28	
19) M.S. Ornamental grill of approved design joints continuously welded with M.S. WI Flats and bars of windows fitted & fixed with necessary screws. Grill weight above 16 kg/m ² = 16 kg/m ² and above	3	0.90	1.20	-	90.72	kg.	88.57	kg.	8035	07	
20) Priming One Coat on timber or plastered surface with synthetic oil bound primer including smoothing surface by sand papering etc.	3	0.90	1.20	2	6.48						
	2	1.05	1.90	-	4.50						
					10.98	m ²	47	m ²	429	68	
21) Priming One Coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothing surface by sand paper	3	0.90	1.20	-	3.24	m ²	31.00	m ²	100	44	
TOTAL RS.									70546	14	

Ruppes

BARANAGAR MUNICIPALITY

The

S. A. ENGINEER / ESTIMATOR

Asst. Engineer
Public Works Dept.

Date

Sanctioned
Chairman
Baranagar Municipality

BARANAGAR MUNICIPALITY

Estimate for

DESCRIPTION	No.	Measurement			Content and Total	Unit	Rate	Per	Amount		Remarks
		L	B	H					Rs.	P.	
22) Priming with best quality synthetic enamel paint including smoothening surface by sand papering etc. including filling putty on the surface on timber with super gloss. Two Coat								B.F.	70546	14	
	3x2	0.90	1.70	-	6.48						
	2	1.05	1.70	-	4.50						
					10.98	m	89.00	m	932	72	
23) Applying exterior grade Acrylic Primer on plaster/concrete surface including scraping and preparing the surface as per manufacturer's specification. Two Coat											
Full side	2	5.20+3.60	3.50		61.6						
Inside	2	4.60+3.05	3.00		45.9						
Ceiling	1	4.60	3.05		14.03						
					121.53	m	48.99	m	5953	75	
24) Protective & decorative Acrylic exterior emulsion over acrylic primer including materials, labour, scaffolding & all incidental charges etc. Two Coat. Premium 100% Acrylic Emulsion											
					121.53	m	92.00	m	11180	76	

Date

Sanctioned Chairman Baranagar Municipality

Ruppes **TOTAL RS. 88613 37**

BARANAGAR MUNICIPALITY

The

S. A. ENGINEER / ESTIMATOR

Asst. Engineer
Public Works Dep