

## BARANAGAR MUNICIPALITY

TENDER NOTICE NO: 031/PW/15-16

No. PW/031/1-15-16

Date: 7/8/15

M/s.....

**SEALED** Tender is invited and will be received by the **Chairman up to 3 P.M of 13.08.2015** for the following work as per terms and condition given below.

The Tender should be addressed to the Chairman, superscripted for " **RENOVATION OF DATA ENTRY ROOM AT HOU BUILDING ( IPPVIII) OF THIS MUNICIPALITY. "**

LAST DATE OF DROPPING- **13..08.2015**

SL. NO	WORK DESCRIPTION	TENDER AMOUNT Rs.	STIPULATED PERIOD
01.	RENOVATION OF DATA ENTRY ROOM AT HOU BUILDING ( IPPVIII) OF THIS MUNICIPALITY.	28,421.00	As per Office Direction.

*m.m. 07/08/15*  
**E.O./F.O.**

*Des 7/8/15*  
**CHAIRMAN.**

### **TERMS & CONDITION**

- 1) Tenders to be submitted in the prescribed tender Form which will have to be obtained from the Municipality at a prescribed cost or Demand draft of Rs.200/- attached with the form downloaded from our website [www.baranagarmunicipality.org](http://www.baranagarmunicipality.org).
- 2) **Tenderer must be registered under " West Bengal Building and other Contribution Welfare Cess ,E.P.F & E.S.I Act. otherwise it will not be treated as valid.**
- 3) **Earnest Money of 2 % of the estimated cost** should be deposited along with the tender.
- 4) The stipulated date for commence / completion of work as per work order issued will have to strictly followed.
- 5) Successful Tenderer (work above Rs.5000/-) shall have to execute a formal Agreement with the Municipality within a week from the date of intimation of the acceptance of his Tender at his own cost & risk.
- 6) The Chairman also reserves the right of accepting of canceling any Tender without assigning any reason thereof.
- 6) If the successful tenderer fails to complete the job within the specified time, a fine of at a stipulated rate( Rs.25/- per day )as fixed by the Municipal Authority will be levied.
- 7) **All Tenders are to be drop in the "Tender dropping Box" kept in the Chairman's room otherwise it will not be treated as valid.**

Estimate No- 001/BMPW/Bldg/15-16

**ESTIMATE FOR RENOVATION OF DATA ENTRY ROOM AT HOU  
BUILDING (IPPVIII)**

SL NO	DESCRIPTION OF ITEMS	UNIT	QUANTITY	RATE	AMOUNT
1)	125mm thick brick work with 1 <sup>st</sup> class bricks in cement mortar(1:4)in ground floor p-31,it-29	M2	11.10	783=00	8691.30
2)	Plaster(to wall,floor,ceiling etc)with sand and cement mortar including rounding off or chamfering comes as directed and raking out joints including throating,nosing and dripcourse,scaffolding/staging where necessary(ground floor ).[Excluding cost of cheeping over concrete surface] With (1:4) cement mortar 15mm thick p-151,it-2/ii/b	sqm	22.20	176=00	3907.20
3)	White washing including cleaning and smoothening the surface thoroughly Two coats(to be done on specific instruction )page-155,item no 3/b.	sqm	63.42	18=87	1196.73
4)	1 Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame excluding cost of concrete, Iron Butt Hinges and M.S clamps. (The quantum should be corrected upto three decimals).p-85,it -1/i	M3	0.062	46171=00	2862.60
5	Supplying solid flush type doors of commercial quality, the timber frame consisting of top and bottom rails and side styles of well seasoned timber 65mm wide each and the entire frame fitted with 37.5mm wide battens placed both ways in order to make the door of solid core and internal lipping with Garjan or similar wood veneers.p-119,it-101/b				

using phenol formaldehyde as glue etc. complete, including fitting, fixing shutters in position but excluding the cost of hinges and other fittings in ground floor p-119,it-101/b.	M2	3.74	2785=00	10415.90
Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark. viii) 100mm. X 75mm. X 3.50mm. p-91,it-20/viii	Each	6	75=00	450.00
i) Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with centre bolt and round fitting. p-93,it -27/i/b	Each	2	184=00	368.00
a) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. p-162,it-7/a(one coat)	M2	4.20	41=00	172.20
A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sandpapering etc. including using of approved putty etc. on the surface, if necessary :p-162 it- 8/A/a/ii(two coat)	M2	4.20	85=00	357.00

Total = 28421.00

Add Contingency 3% = 853.00

Add Cess 1% = 284.00

Gross Total= 29,558.00

(Twenty Nine Thousand Five hundred Fifty Eight only)

*Q*  
29/6/15

*[Signature]*

*Q*  
29/8/15